

CEDAR HOLLOW PROPERTY INSPECTION SERVICES

Comprehensive Property Condition Assessment | Doc ID: DOC-INS-000014

Subject Property:	14 Larkspur Ln	Inspection Date:	April 10, 2025
Client:	Servicing Audit Dept	Inspector:	Robert Jenkins, CMI #9842
Weather:	Clear, 68°F	Property Type:	Single Family Residence
Foundation:	Poured Concrete (Sound)	Roof Condition:	Architectural Shingle (Good)

1. Structural & Building Envelope

Exterior siding, masonry, windows, and door seals were inspected. No active structural settling or significant foundation deflection observed. Roof sheathing and flashing inspected from eaves; estimated remaining useful life 12-15 years.

2. Mechanical, Electrical & Plumbing

Electrical service panel 200A main disconnect; copper branch wiring; GFCI receptacles functional. HVAC system operational on cooling and heating cycles. Water pressure tested at 55 PSI.

[End of Page 1 — Continued on Page 2]

3. Interior Living Areas & Additions / Modifications

Special Finding — Unrecorded Addition: Rear two-story addition completed 2024 under permit #CH-24-0817, approx. 840 sq ft, finished, heated. Construction quality matches main residence. Includes enlarged family room on level 1 and primary suite on level 2. Full HVAC extension confirmed. Note: Public county tax records currently reflect pre-addition GLA of 1,240 sq ft.

4. Inspector Summary & Rating

System	Rating	Comments
Roofing	Good	Normal weathering, no leaks
HVAC	Good	Serviced fall 2024
Plumbing	Satisfactory	No active leaks detected
Overall Condition	C3 (Above Average)	Well maintained residential property